

2 100143

15-155-02323-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 6-10-43
 , SEC. 6, T 23 S, R 9 ~~W&E~~
2970 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Peace Creek Unit Well # 1601W

Operator: Cities Sercie Oil & Gas Corp.

County Reno 122.01

Name & Address 3545 N.W. 58th St.

Well Total Depth 3754 feet

Oklahoma City, OK 73112

~~Conductor~~ Pipe: Size 5 1/2 feet 3720-75 sks.

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated open hole 3720-3754

Plugging Contractor Kelso Casing & Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 7 Month: 5 Year: 19 86

Plugging proposal received from Ron

(company name) Kelso Pulling (phone)

were: spot 50 sacks of cement at total depth - shoot off at 1450' spot cement -
plug from 1450-900; spot a cement plug from 300' to surface.

Plugging Proposal Received by J.L. Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:00 Day: 7 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT Sanded to 3670 feet and dump 5 sacks of cement. Shot pipe
and pulled 1500 feet of 5 1/2". Pump through swedge, 3 sacks of hulls, 9 sacks of gell,
P.S.I. to 1000#. Started pumping cement, 50 sacks then 5 sacks of gel,
and back to 55 sacks of cement, 60/40, 3%. Shut-in and ran hose 20 feet in water
well 6 feet from hole and circulated 10 sacks of cement.

Remarks: Allied Cement Co. #2270; 1500 max psi, 200 S.I. psi
(If additional description is necessary, use BACK of this form.)

5-15-86
STATE CORPORATION COMMISSION
MAY 15 1986
CONSERVATION DIVISION
Wichita, Kansas

observe this plugging.

Signed J.L. Sanders
(TECHNICIAN)
RO

INVOLGED

DATE

INV. NO. 13833