

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 S. Market, Room 2078
Wichita, KS 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-093-00590-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate spud or completion date.

WELL OPERATOR BP AMERICA PRODUCTION COMPANY KCC LICENSE # 5952
(owner/company name) (operator's)
ADDRESS P. O. BOX 3092, WL1, RM 3.315 CITY HOUSTON

STATE TEXAS ZIP CODE 77253-3092 CONTACT PHONE # (281) 366-2052

LEASE JOHNSTON, H. E. WELL # 1 SEC. 17 T. 26S R. 38W (East/West)

C SPOT LOCATION/QQQQ COUNTY KEARNY

2640 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

2640 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL X D&A SWD/ENHR WELL DOCKET # _____

CONDUCTOR CASING SIZE N/A SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 10 3/4" SET AT 646' CEMENTED WITH 425 SACKS

PRODUCTION CASING SIZE 7" SET AT 2465' CEMENTED WITH 350 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4 1/2" LINER @ 2400', 5 1/2" LINER @ 2456' TO 2676'

ELEVATION 3272' T.D. 2676' PBDT _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK RECEIVED
JUNKY (NO HOLES) ON COM.

PROPOSED METHOD OF PLUGGING SEE ATTACHED PROCEDURES

SEP 06 2002

(If additional space is needed attach separate page) CONSERVATION DIVISION
WICHITA, KS

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS.

SUE SELLERS PHONE # (281) 366-2052

ADDRESS P. O. BOX 3092, WL 1, RM 3.315 City/State HOUSTON, TEXAS 77253-3092

PLUGGING CONTRATOR HALLIBURTON SERVICES KCC LICENSE # 5287
(company name) (contractor's)

ADDRESS _____ PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 09/03/02 AUTHORIZED OPERATOR/AGENT: Sue Sellers
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BP America Production Company
2225 West Oklahoma Avenue
Ulysses, KS 67880

September 10, 2002

Re: JOHNSTON #1
API 15-093-00590-00-00
C 17-26S-38W, 2640 FNL 2640 FEL
KEARNY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Plugging Application
H. E. Johnston 1 – Abandonment
Section 17, T26S, R38W
Kearny County

The application attached is to abandon the H.E. Johnston 1. BP America Production Company is abandoning this well due to wellbore integrity.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 06 2002

CONSERVATION DIVISION
WICHITA, KS

**Plugging Procedure for the H. E. Johnston 1
Section 17 T26S R38W
Kearny County, Kansas**

NOTE – NOTIFY KCC DISTRICT OFFICE AT LEAST FIVE DAYS IN ADVANCE OF WORK.

This procedure was approved via a telephone conversation between Cary Spohn (BP representative) and KCC representative Jim Holland on August 29, 2002.

1. Pump 500# of cottonseed hulls in water.
2. Pump 100 sacks of class H, 60/40 poz cement with 6% gel and 2% calcium chloride. Mix cement at 13.2 lb/gal, yield 1.53 cuft/sk.
3. Have 100 sacks of extra cement for annulus between 7" and 10.75" casing.
4. Cut off and cap casing 5' below ground level.
5. Restore location.

RECEIVED
KANSAS COOPERATION COMMISSION

SEP 06 2002

CONSERVATION DIVISION
WICHITA, KS