

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20254-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 32-8S-17W
1028 feet from S Section Line, 2351 feet from E Section Line
Lease Name: LEWIS Well #: 3
County: ROOKS Total Vertical Depth: 3541 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3471		425 SX
SURF	8.625	213		150 SX

Well Type: SWD UIC Docket No: D25217.0 Date/Time to Plug: 05/23/2016 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF BURK Company: MID-CONTINENT ENERGY Phone: (316) 250-5655

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.
Squeezed casing leaks at 943' - 975' w/100 sx cement, 2068' - 2300' w/305 sx cement.
O.H. 3471' - 3541'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2016 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3491' and pumped 11 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1969' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 967' and pumped 100 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing with 25 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 30 sx cement. No pressure. Had cement at surface near well head.

GPS: 39.30960 -099.24039

Remarks: CONSOLIDATED TICKET # 51483

Plugged through: TBG

District: 04

Signed

Pat Bedore

Received
KANSAS CORPORATION COMMISSION

JUN 24 2016

CONSERVATION DIVISION
WICHITA, KS

(TECHNICIAN)

NO
JUL -7 2016
cc UIC

CM

Form CP-2/3