

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20433-00-02
Spot: NWNW Sec/Twnshp/Rge: 20-34S-19W
4645 feet from S Section Line, 4574 feet from E Section Line
Lease Name: LEMON RANCH Well #: 2-20
County: COMANCHE Total Vertical Depth: 5375 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4438		WITH 10 SX CMT
PROD	4.5	5373	0	
SURF	8.625	655		

Well Type: SWD UIC Docket No: D28486.0 Date/Time to Plug: 06/02/2016 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4438' WITH 10 SX CMT. PLUG AT 850' WITH 75 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/02/2016 9:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4438' WITH 10 SX CMT. POOH WITH TBG. CUT CASING AT 1210' BUT DIDN'T GET LOOSE. DUG OUT CELLAR & FOUND NO BRADEN HEAD BUT CASING WAS CEMENTED TO SURFACE. PRESSURED TESTED CASING TO 300#. RAN TBG TO 1240' & PUMPED 80 SX CMT. POOH WITH TBG & TOPPED OFF WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4488	4516		

Received
KANSAS CORPORATION COMMISSION
JUN 10 2016
CONSERVATION DIVISION
WICHITA, KS
6-10-16

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]
SA (TECHNICIAN)

RECEIVED
JUN - 6 2016
KCC DODGE CITY [Signature]

Form CP-2/3
JUL - 7 2016
CC UIC