

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-20259-00-00
Spot: NWSESW Sec/Twnshp/Rge: 26-33S-6W
617 feet from S Section Line, 4613 feet from E Section Line
Lease Name: MEINEKE Well #: 3
County: HARPER Total Vertical Depth: 4544 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3674		100 SX
SURF		203		
SURF	8.625	209		190 SX

Well Type: SWD UIC Docket No: D19239.0 Date/Time to Plug: 06/09/2016 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERISES Phone:

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/14/2016 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET 5 1/2" CIBP @ 3508', LOADED HOLE WITH MUD, SPOTTED 20 SKS ON CIBP. RECOVERED 1158' OF 5 1/2" CASING & PULLED FROM WELL. RAN TUBING TO 1150' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 700', SPOTTED 35 SX CEMENT. PULLED TUBING TO 250' & CIRCUALTED HOLE TO SURFACE WITH 85 SKS.


Perfs:

Top	Bot	Thru	Comments
3558	3624		

Remarks: CLASS C CEMENT. ORR ENTERPRISES. FAILED MIT

Plugged through: TBG

District: 02

Signed 

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JUN 23 2016
CONSERVATION DIVISION
WICHITA, KS

NO
JUL -7 2016
cc uic Form CP-2/3

JK