

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-22611-00-01  
Spot: SWSWNE Sec/Twnshp/Rge: 3-17S-21W  
2969 feet from S Section Line, 2267 feet from E Section Line  
Lease Name: LAMER Well #: 1  
County: NESS Total Vertical Depth: 4210 feet

Operator License No.: 30104  
Op Name: CAMBRON, PAUL L.  
Address: 118 N PENN PO BOX 384  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4209	0	WITH 350 SX CMT
SURF	8.625	386		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2016 10:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: HAL HOSS Company: PAUL L. CAMBRON Phone: (785) 798-5051

Proposed Plugging Method: PUMP 30 SX CMT ON BOTTOM. PLUG AT 1500' WITH 30 SX CMT. PUMP CMT FROM 850' TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/06/2016 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

\*\*ORIGINAL INTENT SHOWED THAT THE 5 1/2" WAS CEMENTED FROM 4210' TO SURFACE.\*\* PUMPED 30 SX CMT ON BOTTOM. 1ST PLUG AT 1500' WITH 30 SX CMT. 2ND PLUG AT 850' WITH 70 SX CMT. PULLED TBG & TOPPED OFF WITH 25 SX CMT. PRESSURED THE BACKSIDE WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4106	4112		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
JUN 10 2016  
KCC DODGE CITY

Form CP-2/3  
JUL -7 2016