

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-23661-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 27-23S-10E  
4950 feet from S Section Line, 1735 feet from E Section Line  
Lease Name: BURKETT E Well #: 42  
County: GREENWOOD Total Vertical Depth: 2390 feet

Operator License No.: 33245  
Op Name: CROSS BAR ENERGY, LLC  
Address: 1700 N. WATERFRONT PKWY BLDG 3  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2389		125 SX
SURF	8.625	212		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2016 8:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STUART WOODIE Company: \_\_\_\_\_ Phone: (316) 239-6151

Proposed Plugging Method: 20 SKS @ 2390'; 20 SKS @ 900'; 30 SKS @ 150' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/09/2016 11:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

rig up to tubing pumped 20 sxs cement @ 2374, pulled tubing to 911' pumped 20 sxs cement, pulled tubing to 150' pumped 50 sxs cement to surface, gel spacers between cement plugs.

RECEIVED  
KCC DIST # 3  
JUN 13 2016  
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

KCC WICHITA

JUN 17 2016

RECEIVED

7-1-16

no  
JUL -7 2016

Form CP-2/3

810 E 7TH  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



Cement or Acid Field Report  
 Ticket No. 2822  
 Foreman Stewart Wood  
 Camp Eureka

15-073-23661

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-9-16	1038	BURKETT # E-42	27	23	10E	Greenwood	Ks
Customer			Unit #	Driver	Unit #	Driver	
Cross Bar Energy LLC			104	Alan M			
Mailing Address			110	Alan B			
1700 N Waterfront PKWY			141				
City	State	Zip Code					
Wichita	Ks	67206					

Job Type PTA Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety meeting. Rig up to 2 3/8 Tubing. Pump 9 bbls water ahead spot 20 sks cement at 2374'. Pull tubing up to 911'. Break circulating w/ water spot 20 sks cement at 911'. Pull tubing up to 150'. Break circulation. Mix 50 sks cement 150' to surface. Shut well in. Job complete Rig down

(Note Pump 300# Gel flush ahead of first cement plug)

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105-2	1	Pump Charge	500.00	500.00
C107	-	Mileage <u>N/C</u>	-	
C203	90 sks	6 1/4 202 mix Cement	12.75	1147.50
C206	300#	Gel 420	.20	60.00
C206	300#	Gel Flush	.20	60.00
C108A	3.87 ton	Ton Mileage Bulk Truck	<u>M/C</u>	345.00
C113	2 hr	80 bbl Gas Truck	85.00	170.00
KCC WICHITA				
JUN 17 2016				
RECEIVED				
			Sub Total	2282.50
			Sales Tax	171.19

Authorization Witness by Stewart Wood Title Co. Rep. Total 2453.69

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.