

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23103-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 12-21S-11W
1230 feet from N Section Line, 430 feet from W Section Line
Lease Name: SESSLER TRUST Well #: 1-12
County: STAFFORD Total Vertical Depth: 3500 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3496	1450	WITH 175 SX CMT
SURF	8.625	202		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2016 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT WITH 100# HULLS ON BOTTOM. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 05/24/2016 3:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

PUMP 30 SX CMT WITH 100# HULLS ON BOTTOM. TAGGED BOTTOM PLUG AT 3274'. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3346	3357		

Received
KANSAS CORPORATION COMMISSION
JUN 10 2016
CONSERVATION DIVISION
WICHITA, KS
6-10-16

Remarks: USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY.

Plugged through: CSG

District: 01

Signed

Ken Scofield

(TECHNICIAN)

RECEIVED
MAY 31 2016
KCC DODGE CITY

JUL -7 2016 Form CP-2/3