

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21489-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 36-22S-17W
2303 feet from S Section Line, 2226 feet from E Section Line
Lease Name: AMF FARMS-FRICK Well #: 1
County: PAWNEE Total Vertical Depth: 4372 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 5.5 | 4372 | 1450 | WITH 125 SX CMT |
| SURF | 8.625 | 713 | | WITH 250 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/14/2016 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SAND TO 4070' WITH 5 SX CMT. PLUG AT 1120' WITH 12 SX GEL & 50 SX CMT. PLUG AT 760' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 06/14/2016 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BACK TO 4070' & TOP WITH 5 SX CMT. TAGGED BOTTOM PLUG AT 4040'.
1ST PLUG AT 1115' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 760' WITH 50 SX
CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 80 SX CMT TO
SURFACE. 6/15/16: CMT FELL BACK TO ABOUT 100' MEASURED BY STRING LINE.
PUMPED ANOTHER 25 SX CMT TO FILL CASING.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4180 | 4183 | | |
| 4150 | 4150 | | |
| 4120 | 4124 | | |

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

Ken Scofield

(TECHNICIAN) *SA*

RECEIVED
JUN 23 2016
KCC DODGE CITY

Form CP-2/3

JUL 7 2016