

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20742-00-00
Spot: SENWSE Sec/Twnshp/Rge: 24-15S-12W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HEINZE (TWIN) Well #: 5
County: RUSSELL Total Vertical Depth: 3393 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3393		225 SX
SURF	8.625	250		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/26/2016 9:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: G.L.M. CO. Phone: (785) 639-5415

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Ordered an additional 200 sx 60/40 pozmix 4% gel cement.
Cleaned casing down to 3224'. Hit iron and could not make any more hole. Started to lose circulation.
AD-1 packer and tubing anchor was left in well at an early date.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2016 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 250' and 740'. Ran tubing to 3192' and pumped 25 sx cement followed by 75 sx cement w/200 # hulls. Pulled tubing to 2500' and pumped 150 sx cement w/400 # hulls (Had a blow out on backside). Pulled tubing to 800' and pumped 150 sx cement w/200 # hulls. AD Fluid to surface after pumping 50 sx on braden head and surface. Ran out of cement. Pumped 150 sx down cement. Fluid in casing down 20' - 25'. Ordered 200 sx cement. Hooked to casing and pumped 150 sx cement w/no blow on the braden head. Hooked to braden head and pumped 50 sx cement down at 200 - 250 psi.
06/06/2016- Fluid down 15' - 20'.

GPS: 38.73084 -098.60232

Perfs:

Top	Bot	Thru	Comments
3323	3329		
3259	3261		
3183	3185		
3097	3099		
3065	3067		
3039	3041		
3030	3034		
2920	2925		
2854	2856		
2842	2844		
2834	2836		

Remarks: GLOBAL CEMENTING TICKET # 2592

Plugged through: TBG

District: 04

Signed: Ray Dinkel (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUN 24 2016

CONSERVATION DIVISION
WICHITA, KS

CM
No: _____
JUL -7 2016 Form CP-2/3

JUN 14 2016