

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25912-00-00
Spot: SENESESW Sec/Twnshp/Rge: 17-18S-24W
741 feet from S Section Line, 2357 feet from W Section Line
Lease Name: VERNON Well #: 1
County: NESS Total Vertical Depth: 4430 feet

Operator License No.: 33605 String Size Depth (ft) Pulled (ft) Comments
Op Name: JOE GERSTNER OIL, LLC SURF 8.625 219 WITH 150 SX CMT
Address: PO BOX 509
NESS CITY, KS 67560

Well Type: DH UIC Docket No: Date/Time to Plug: 06/10/2016 8:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Revd. from: KIRBY STRUTT Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1660' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 80 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE
Date/Time Plugging Completed: 06/10/2016 10:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 1660' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 80 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OILWELL.

Plugged through: DP

District: 01

Signed Larry Harris EC25
(TECHNICIAN)
SA

RECEIVED
JUN 13 2016
KCC DODGE CITY

Form CP-2/3

NO
JUL -7 2016