

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20225-00-00
Spot: SESESW Sec/Twnshp/Rge: 4-22S-33W
659 feet from S Section Line, 3252 feet from E Section Line
Lease Name: NORMAN ADAMS Well #: 1-4
County: FINNEY Total Vertical Depth: 4798 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1963		WITH 2 SX CMT
CIBP		4280		
PROD	5.5	4798	0	WITH 200 SX CMT
SURF	8.625	481		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2016 8:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Revd. from: KENT STRUBE Company: HARTMAN OIL Phone: (620) 786-4161

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP AT 4280'. RUN BOND LOG FROM 3800' TO 0'. FOUND TOC @ 550'. HAVE CMT FROM 3800' TO 550' DUE TO PREVIOUS CEMENT SQUEEZE JOBS AND POSSIBLE PREVIOUS ANNULAR SQUEEZE. NO RECORD OF A STAGE TOOL OR PERFORATING FOR ALTERNATE II ON ORIGINAL COMPLETION. SET CIBP @ 1963' WITH 2 SX CMT. PERFORATE 4 HOLES AT 500'. RUN TBG TO 1150' & CIRCULATE CMT TO 500'. TOOH WITH TBG & CIRCULATE CMT FROM 500' TO SURFACE USING 185 SX CMT, LEAVING THE CASING AND ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
4382	4395		
4320	4328		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUN 28 2016
KCC DODGE CITY

no Form CP-2/3
JUL -7 2016