

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-02657-00-00
Spot: NENESWNW Sec/Twnshp/Rge: 9-33S-14E
3709 feet from S Section Line, 3993 feet from E Section Line
Lease Name: PATTERSON/AGOSTO Well #: 11
County: MONTGOMERY Total Vertical Depth: 1260 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	1200		0 SX
PROD	4.5	1250		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 03/18/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1140' gelled hole and spotted 10 sack plug. Pulled up to 600' and spotted 5 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 40 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1206	1210		

RECEIVED
KCC DIST # 3
JUN 17 2016
CHANUTE, KS
DS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JUN 23 2016
CONSERVATION DIVISION
WICHITA, KS

6-23-16

Form CP-2/3
JUL -7 2016