

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-159-20537-00-01
 Spot: S2S2N2SW Sec/Twnshp/Rge: 21-20S-10W
1360 feet from S Section Line, 3960 feet from E Section Line
 Lease Name: SESSLER Well #: 1
 County: RICE Total Vertical Depth: 3356 feet

Operator License No.: 5210
 Op Name: LEBSACK OIL PRODUCTION INC.
 Address: PO BOX 354
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2475		
CIBP	5.5	2570		
CIBP		3250		
CIBP		3308		
PROD	5.5	3348	1615	125 SX
SURF	8.625	248		225 SX
T1	2.375	3304		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2016 12:30 PM
 Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
 Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 546-3388

Proposed Plugging Method: AS PER KCC RULES & REGS CIBP'S @ 3250' AND 3308' ALSO.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
 Date/Time Plugging Completed: 06/08/2016 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
 MIRU, RUN DOWN TO TOP CIBP @ 2570'. SET CIBP @ 2475' AND CAP WITH 2 SX'S CEMENT. CUT CASING OFF AT 1615' AND PULL TO 1300' AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC. PULL CASING TO 900' AND WAIT FOR 45 MINUTES. TAG CEMENT AT 1150' WITH SWAB BAR. PUMP 35 SX'S AT 900', PULL CASING TO 300' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Received
 KANSAS CORPORATION COMMISSION
JUN 21 2016
 CONSERVATION DIVISION
 WICHITA, KS

Perfs:

Top	Bot	Thru	Comments
3310	3314		CSG
3309			CSG
3304	3314		CSG
3074	3095		CSG
2524	2528		CSG

Remarks: BASIC SERVICES TICKET #13647. EXPIRED TA

Plugged through: CSG

District: 02

Signed Virgil Clothier (TECHNICIAN) No
JUL -1 2016