

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00400-00-02
Spot: NENESE Sec/Twnshp/Rge: 35-28S-8W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: BIGGS Well #: 1-35
County: KINGMAN Total Vertical Depth: 4705 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: PO BOX 1278
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4010		
PKR		3960		
PROD	5.5	4544		150 SX
SURF	8.625	127		100 SX
T1	2.375	3960		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/02/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/03/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP WAS ALREADY SET AT 4010' WITH 2 SX OF CEMENT ON TOP. PERFORATED AT 1200', 750', AND 250', RAN TUBING TO 1200', PUMPED 35 SACKS, 3% CC 100# HULLS, PULLED TUBING OUT, TAGGED CEMENT AT 860', RAN TUBING TO 750', PUMPED 35 SACKS COMMON CEMENT, 100# HULLS, PULLED TUBING TO 250', PUMPED 65 SACKS COMMON CEMENT, PULLED TUBING OUT HOOKED UP TO 5 1/2" CASING, PUMPED 50 SACKS COMMON CEMENT, CIRCUALTED OUT SURFACE. NEXT DAY 6/3/16 EMPTIED PIT, DUG OUT AROUND CASING, CUT WELL HEAD OFF, TOPPED WELL WITH 35 SACKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4068	4076		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB ALSO.

Plugged through: TBG

District: 02

KCC WICHITA
JUN 29 2016
RECEIVED

Signed



(TECHNICIAN)

MO
JUL 7 2016