

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20266-00-01
Spot: SESENE Sec/Twnshp/Rge: 23-28S-8W
3150 feet from S Section Line, 510 feet from E Section Line
Lease Name: PRAY Well #: 1
County: KINGMAN Total Vertical Depth: 4415 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: PO BOX 1278
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4415		100 SX
SURF	8.625	207		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/01/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/03/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP WAS ALREADY SET (3970'). TAGGED PLUG AT 3970', BAILED 2 SACKS CEMENT ON PLUG, PERFORATED AT 1200', 750', AND 260', RAN TUBING TO 1200', PUMPED 35 SACKS COMMON CEMENT, 3% CC, 100# HULLS, PULLED TUBING OUT, CHECKED HOLE, TAGGED PLUG AT 835', RAN TUBING TO 750', PUMPED 35 SACKS CEMENT, PULLED TUBING TO 260', PUMPED 70 SACKS CEMENT, PULLED TUBING OUT, HOOKED UP TO 5 1/2" CASING, PUMPED 40 SACKS CEMENT, HOOKED UP TO 8 5/8", PUMPED 10 SACKS CEMENT, NEXT DAY CUT HEAD OFF TOPPED OFF WELL WITH 10 SACKS.

Perfs:

Top	Bot	Thru	Comments
4048	4060		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB ALSO.

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

NO
JUL -7 2016

KCC WICHITA
JUN 29 2016
RECEIVED