

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-00890-00-00
Spot: NENWSW Sec/Twnshp/Rge: 23-31S-9W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: MARTIN B Well #: 5
County: HARPER Total Vertical Depth: 4502 feet

Operator License No.: 32825
Op Name: PIONEER EXPLORATION, LLC
Address: 15603 KUYKENDAHL STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		
CIBP		4400		
PROD 7		4502	250 SX	
SURF 10.75		323	250 SX	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/16/2016 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PULLED & LAYED DOWN RODS. TRIED TO PULL TUBING, STUCK IN HOLE. SHOT TUBING AT 3214' PUMPED 130 SKS CEMENT. CEMENT CAME UP HOLE, TAGGED AT 1100', DRILLED CEMENT OUT TO 1500', WHERE WE PERF'D AT 1500', TAGGED CEMENT AT 1100'. SPOT 50 SX AT 1000'. PULLED TUBING TO 380' AND PUMPED 123 SX CEMENT, LAYED DOWN TUBING & BULL HEAD CEMENT DOWN 7" & BACK UP 10 3/4 WITH 180 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4423	4428		
4140	4150		
4075	4079		
4045	4050		
3791	3796		
3284	3294		
3170	3180		

Remarks: COMMON CEMENT. QUALITY WELL SERVICE. DENIED TA

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUN 23 2016

CONSERVATION DIVISION
WICHITA, KS

no
JUL -7 2016

Form CP-2/3