

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21003-00-00
Spot: W2 Sec/Twnshp/Rge: 7-35S-29W
1265 feet from N Section Line, 649 feet from W Section Line
Lease Name: WYNONA Well #: 1
County: MEADE Total Vertical Depth: 6440 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30604</u>	CIBP		6280		WITH 2 SX CMT
Op Name: <u>RAYDON EXPLORATION, INC.</u>	PROD	5.5	6440	2250	WITH 100 SX CMT
Address: <u>1601 NW EXPRESSWAY, STE 1300</u> <u>OKLAHOMA CITY, OK 73118</u>	SURF	8.625	1638		WITH 550 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/15/2016 10:00 AM
Plug Co. License No.: 34727 Plug Co. Name: PARTNERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: RONNIE MORRISON Company: PARTNERS OILFIELD SERVICES, L Phone: (307) 587-4291

Proposed Plugging Method: SET CIBP @ 6280' WITH 2 SX CMT. PLUG AT 1680' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/15/2016 4:25 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 6280' WITH 2 SX CMT. 1ST PLUG AT 1689' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 552' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6321	6327		

Remarks: USED 60/40 POZMIX 4% GEL BY PARTNERS OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUN 21 2016
KCC DODGE CITY

JUL 7 2016

Form CP-2/3