

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21874-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 26-9S-22W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: CHRISTINE BARBER Well #: 1  
County: GRAHAM Total Vertical Depth: 3930 feet

Operator License No.: 6677  
Op Name: SANDLIN OIL CORPORATION  
Address: 621 17TH ST STE 2055  
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3929		150 SX
SURF	8.625	218		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/01/2016 12:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: FRED BARBER Company: SANDLIN OIL CORPORATION DBA Phone: (785) 623-3151

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Port Collar at 1820' w/500 sx cement.  
Perforations: 3888' - 3904', 3859', 3798', 3778', 3733' - 3737', 3774' - 3778', 3797' - 3799'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2016 3:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3775' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2975' and pumped 75 sx cement. Pulled tubing to 1975' and pumped 75 sx cement. Pulled tubing to 975' and pumped 65 sx cement. Good circulation of cement. Pulled tubing out and topped off casing w/10 sx cement. Cement to surface on backside.

GPS: 39.24049 -099.75272

Perfs:


Top	Bot	Thru	Comments
3888	3904		
3859	3860		
3798	3799		
3797	3799		
3778	3779		
3774	3778		
3733	3737		

Remarks: QUALITY CEMENT TICKET # 1971

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

JUN 14 2016

JUN 24 2016

JUL -7 2016 Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS