

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21417-00-00
Spot: NWNWSEW Sec/Twnshp/Rge: 6-6S-28W
1605 feet from N Section Line, 1541 feet from W Section Line
Lease Name: JOHNSON Well #: 1-6
County: SHERIDAN Total Vertical Depth: 4515 feet

Operator License No.: <u>35245</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>SUEMAUR EXPLORATION & PRODUCT</u>	<u>SURF</u>	<u>8.625</u>	<u>261</u>		<u>250 SX</u>
Address: <u>539 N. CARANCAHUA SUITE 1100</u>					
<u>CORPUS CHRISTI, TX 78401</u>					

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/13/2016 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY Company: MURFIN DRILLING CO., INC. Phone: (785) 769-6103

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE
Date/Time Plugging Completed: 06/13/2016 5:00 PM KCC Agent: CHRIS NEELEY

Actual Plugging Report: _____ Perfs: _____

1st plug @2580 w/50 sx
2nd plug @1780 w/100 sx
3rd plug @320 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED
Plugged through: DP

District: 04 Signed Chris Neeley (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JUN 24 2016
CONSERVATION DIVISION
WICHITA, KS
JUL -7 2016
Form CP-2/3