

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-20599-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 16-12S-33W
660 feet from N Section Line, 990 feet from W Section Line
Lease Name: VOTH #1-16 Well #: 1-16
County: LOGAN Total Vertical Depth: 4700 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 4695 | | 200 sx |
| SURF | 8.625 | 355 | | 190 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2016 8:00 AM
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC
Proposal Rcvd. from: JOE RUPP Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 2605' w/400 sx cement.
Perforations: 4273' - 4277'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2016 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 4285' and pumped 50 sx cement w/150 # hulls. Pulled tubing to 3628' and pumped 75 sx cement. Pulled tubing to 2377' and pumped 75 sx cement. Pulled tubing to 1564' and pumped 90 sx cement. Good circulation of cement. Pulled tubing out and topped off casing w/19 sx cement. Tied on to backside and squeezed w/7 1/2 sx cement. Shut in pressure 350 psi.

GPS: 39.01590 -100.99561

Remarks: BASIC CEMENT TICKET # 171813659

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN) *no* *cr*

Received
KANSAS CORPORATION COMMISSION

JUN 24 2016

CONSERVATION DIVISION
WICHITA, KS

MAY 31 2016

JUL -7 2016

Form CP-2/3