

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-26365-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 25-26S-19E
565 feet from N Section Line, 860 feet from W Section Line
Lease Name: ARD Well #: 5
County: ALLEN Total Vertical Depth: 658 feet

Operator License No.: 5491
Op Name: W & W PRODUCTION COMPANY, GEN
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	658		110 SX
SURF	6.5	25		6 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2016 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSETT Company: _____ Phone: (620) 431-4137

Proposed Plugging Method: Squeeze Well. Hook up on top of well & pump cement to TD.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 05/13/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled 1" pipe out of the casing. Washed 1" pipe down the backside of the 2" casing to 325' where cement was encountered, Pumped and circulated cement through the 1" pipe on the backside of the 2" casing from 325' to surface. Pulled 1" pipe and topped the well off with cement. A total of 44 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JUN 16 2016
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUN 20 2016

CONSERVATION DIVISION
WICHITA, KS

6-20-16

JUL -7 2016

Form CP-2/3