

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24585-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 1-12S-16W
4831 feet from S Section Line, 4634 feet from E Section Line
Lease Name: NATIONAL LOAN COMPANY Well #: 2-1
County: ELLIS Total Vertical Depth: 3320 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3318		100 SX
SURF	8.625	584		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2016 8:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: JEFF BURKE Company: MID-CONTINENT ENERGY Phone: (316) 250-5655

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 800 # hulls.
Perforations: 3136' - 3220' - 3188' - 3320' - 3203' - 3211'.
Pulled tubing to 1601'. Parted rods tops at 1476'.
District Supervisor approved plug.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2016 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

E.L.I. perforated at 1476', 950' and 580'. Leiker Well Service ran in hole to 1600'. Quality rigged to tubing, mixed and pumped 200 sx to circulate cement up 4 1/2" and 8 5/8" casing. Pulled tubing. Rigged to 4 1/2" casing with a swedge. Shut in backside on 8 5/8" casing and pressured 4 1/2" and 8 5/8" casing to 700 psi. Shut in pressure 700 psi w/70 sx 60/40 pozmix 4% gel cement.

GPS: 39.04396 -099.05437

Perfs:

Top	Bot	Thru	Comments
3203	3211		

Remarks: QUALITY WELL SERVICE TICKET # 1969

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

JUN 24 2016

CONSERVATION DIVISION
WICHITA, KS

(TECHNICIAN)

JUL -7 2016

Form CP-2/3