

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21766-01-00
Spot: NENWSWSW Sec/Twnshp/Rge: 20-30S-20W
1215 feet from S Section Line, 4722 feet from E Section Line
Lease Name: MICHAEL 3020 Well #: 1-20H
County: KIOWA Total Vertical Depth: 5660 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1800		WITH 20 SX CMT
CIBP		5700		WITH 50 SX CMT
COND 20		110		WITH 10 YDS CMT
PROD 7		5926	1226	WITH 265 SX CMT
SURF 9.625		783		WITH 335 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2016 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5700' WITH 50 SX CMT. PLUG AT 1200' WITH 60 SX CMT. PLUG AT 830' WITH 80 SX CMT. 330' CIRCULATE TO SURFACE WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2016 12:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5700' WITH 50 SX CMT. FOUND A HOLE IN THE 7" CASING AT 2762'.
SET CIBP @ 1800' WITH 20 SX CMT. 1ST PLUG AT 1200' WITH 60 SX CMT. 2ND
PLUG AT 833' WITH 80 SX CMT. 3RD PLUG AT 330'. CIRCULATED CMT TO
SURFACE WITH 110 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6178	6181		
6123	6126		
6070	6076		
6024	6027		
5948	5987		
5941	7307		


Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
JUN 29 2016
KCC DODGE CITY

Signed


SA (TECHNICIAN)

(TECHNICIAN)

no
JUL -7 2016

Form CP-2/3