

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21822-01-00  
Spot: N2N2NWNW Sec/Twnshp/Rge: 10-35S-7W  
250 feet from N Section Line, 660 feet from W Section Line  
Lease Name: WESLEY Well #: 1-10H  
County: HARPER Total Vertical Depth: 4845 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		10 sx cement
I1	7	5278		300 sx cement
L1	4.5	9999		756 sx cement
PROD	7	5284	1422	300 SX
SURF	9.625	836		580 SX
SURF	9.63	850		580 sx cement

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/15/2016 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: BRENT MORRIS Company: \_\_\_\_\_ Phone: (405) 429-6002

Proposed Plugging Method: TD 12453'; TVD 4845'. See Attached proposed plugging procedure, contingent on KCC District Staff Approval.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/20/2016 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

RAN IN HOLE WITH 7" CIBP ON TUBING. SET CIBP AT 4050', CIRCULATED MUD TO SURFACE. SPOTTED 20 SX CEMENT ON CIBP. RECOVERED 1422' OF 7" CASING, PULLED FROM WELLBORE. RAN 2 7/8" TUBING TO 1250'; SPOTTED 50 SX CEMENT. PULLED TUBING TO 870', SPOTTED 50 SX CEMENT. PULLED TUBING TO 250' & CIRCULATED CEMENT TO SURFACE WITH 8 5/8" 85 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
8330	8777		
7773	8220		
7216	7664		
6708	7107		
6118	6551		
5547	5994		
4990	9999		


Remarks: CLASS C CEMENT. ORR ENT. TMD = 12,453

Plugged through: TBG

District: 02

Received  
KANSAS CORPORATION COMMISSION  
JUN 23 2016  
CONSERVATION DIVISION  
WICHITA, KS

Signed



(TECHNICIAN)

*No.*  
JUL -7 2016