

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-19201-00-00  
Spot: SENWSWNE Sec/Twnshp/Rge: 27-23S-10E  
1950 feet from N Section Line, 2200 feet from E Section Line  
Lease Name: BURKETT Well #: E-23  
County: GREENWOOD Total Vertical Depth: 2329 feet

Operator License No.: 33245  
Op Name: CROSS BAR ENERGY, LLC  
Address: 1700 N. WATERFRONT PKWY BLDG 3  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.1875	2262		100 SX
SURF	6.875	1650		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2016 11:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STUART WOODIE Company: \_\_\_\_\_ Phone: (316) 239-6151

Proposed Plugging Method: 20 SKS @ 2262'; 20 SKS @ 900'; 30 SKS @ 150' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/09/2016 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

rig up to tubing pumped 20 sxs cement @ 2248',pulled tubing to 911'pumped 20 sxs,pulled tubing to 150' pumped 70 sxs cement to surface,gel spacers between cement plugs.

RECEIVED  
KCC DIST # 3  
JUN 13 2016  
CHANUTE, KS

mtt

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

KCC WICHITA

JUN 17 2016

RECEIVED

6-17-16

JUL -7 2016 Form CP-2/3

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



Cement or Acid Field Report  
 Ticket No. 2821  
 Foreman Steve Mead  
 Camp Eureka

APT 15-073-19261

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-9-16	1038	BUCKET #E-23	27	23	16	Greenwood	Ks
Customer			Unit #	Driver	Unit #	Driver	
CrossBar Energy LLC			104	Alan M			
Mailing Address			110	Allen B			
1700 N. Waterfront Pkwy			141				
City	State	Zip Code					
Wichita	Ks	67206					

Job Type PIA Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 228  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 Cement Left In Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting. Rig up to 2 3/8 tubing. Pump 8 bbls water ahead. Mix 200# Gel Flush. Spot 200# cement AT 2248'. Pull tubing up to 911'. Rig back up to tubing. Break circulation w/ water. Spot 200# cement AT 911'. Pull tubing OUT to 150'. Break circulation w/ fresh water. Mix 200# cement 150' to surface. Shut well in.  
Job complete Rig down

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	n/c	Mileage		0
C203	110SKS	60/40 Permix Cement	12.75	1402.50
C206	375#	Gel 4%	.20	75.00
C206	300#	Gel Flush	.20	60.00
C108A	4.7370n	Ten mileage Bulk Truck	n/c	345.00
C112	2hr	8000l Uac Truck	85.00	170.00
KCC WICHITA				
JUN 17 2016				
RECEIVED				
			Sub Total	2802.50
			Sales Tax 2.50%	210.19
				Total 3012.69

Authorization - Called by Stewart Wood Title Co. Rep Total 3012.69

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.