

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

NOV 4 1966
11-04-66
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Kansas-Nebraska Natural Gas Co., Inc.

Complete Address: Box 608, Hastings, Kansas

Lease Name Turner Well No. 1

Location App. Center 23 Sec. 28 Twp. 24 Rge. 38 (W)

County Kearny Total Depth 2650'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casings Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 1:30PM Day 2 Month 11 Year 1966

The Above well was plugged as follows:

10 3/4" to 402' ciru, w/ cement. 7" to 2643' cirulated w/ cement.

Top Perforations 2404' Plug bottom w/ 30 sacks cement.

Top of cement 2090' Mud 2090' to 500'

Spot 20 sacks cement 500' to 400' Mud 400' to 50'

Plug, Hulls & 10 sacks cement 50' to 0'

No Casing Pulled. Company Pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edmund J. Laves
Well Plugging Supervisor

DATE 11/4/66

INV. NO. 4228-u