

15-095-19037-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1964

01-20-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name _____ Brand _____ Well No. # 2

Location SW SE NE Sec. 32 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4268

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Co., Inc.

Address: Box 221, Great Bend, Kansas License No. _____

Operation Completed: Hour 3:00PM Day 18th Month Jan. Year 1964

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cement circulated. 4268' of 5 1/2" long string,
cemented with 150 sacks. Plug back to 4244'. Top perferation 4180'. Bottom
of hole was sanded to 4170', and cemented with 5 sacks. Fluid level in
hole was 275'. Plug was set at 275', with 10' rock bridge, and cemented
with 30 sacks, bringing the cement to 170' in surface pipe. Hole was
filled with mud to 40', 10' rock bridge, and cemented with 10 sacks to
base cellar.

3224' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/21/64
INV. NO. 8489-cc