

KANSAS

15-095-19038

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl Bank Bldg. Wichita, Ks 67202

Lease Name Brand Well No. 3

Location SW/NW/NE Sec. 32 Twp. 29 Rge. 7 (E) (W) X

County Kingman Total Depth 4237

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Inc.

Address Box 1082 Great Bend, Ks 67530 License No. 623

Operation Completed: Hour 3:00PM Day 7 Month 3 Year 1970

The above well was plugged as follows:

236 ft of 8 5/8 surface pipe circulated with 165 sacks cement.

4237 ft of 5 1/2 long string cemented with 110 sacks. Top perf. 4145-50

ft. Sand back to 4050 ft, 5 sacks cement with bailer. Pulled

3457 ft of 5 1/2. Mud 230, 10 ft rock bridge, 25 sacks cement. Mud

to 40 ft, 10 ft rock bridge, 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-9-70

INV. NO. 1558-w

Signed: L. Russell B. Shurtlee
Well Plugging Supervisor