

*16*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-095-19039-~~0000~~

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

*PLUG  
11-09-65*

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Brand Well No. # 4

Location C S/2 NE NE Sec. 32 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4279'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 1:30 PM Day 27th Month Oct. Year 1965

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cemented with 160 sacks. 4272' of 5 1/2" long  
string, cemented with 100 sacks. Plug back to 4234'. Top perferation  
4175'. Bottom of the hole was sanded to 4160', and cemented with 5 sacks.  
3770' of 5 1/2" long string was recovered from the hole. Hole was filled  
with mud to 250', rock bridge from 250' to 240', and cemented with 25  
sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',  
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 11/9/65  
INV. NO. 2147-u