

15-095-00736-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

JAN 14 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl Bldg. Wichita, Ks

Lease Name Birkenbaugh B Well No. 1

Location NE/NE/NE Sec. 33 Twp. 29 Rge. 7 (E) (W)

County Kingman Total Depth 4240

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 4:00 PM Day 13 Month 1 Year 1971

The above well was plugged as follows:

250 ft of 8 5/8 surface pipe cemented with 100 sacks. 4233 ft of 4 1/2

long string cemented with 100 sacks. Top perf. 4156 to 78 ft.

Sand back to 4125 ft, 4 sacks cement with bailer. Pulled 309 ft of

4 1/2. Set 10 ft rock bridge at 240 ft. Fill hole with 4 yds of redimix
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Behestin
Well Plugging Supervisor

DATE 1-14-71

INV. NO. 3211-W