

W
KANSAS
STATE CORPORATION COMMISSION

15-095-19041-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 9 1963
07-09-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name Berkenbaugh "B" Well No. # 3

Location NW SE NE Sec. 33 Twp. 29 Rge. 7 (E) (W)W

County Kingman Total Depth 4270

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Kent Well Servicing Co.

Address: Box 470, Eldorado, Kansas License No. 394

Operation Completed: Hour 4:00PM Day 2nd Month July Year 1963

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cement circulated with 145 sacks.

4269' of 5 1/2" long string, cemented with 100 sacks. Top perforation

4193'. Sandeā to 4180', cemented with 5 sacks. Hole was filled with

mud to 235', 10' rock bridge, cemented with 20 sacks. Hole was filled

with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.

3660' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving

Well Plugging Supervisor

DATE 7/9/63

INV. NO. 7386-W