

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. \_\_\_\_\_

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP \_\_\_\_\_

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

Letter requesting confidentiality attached.

C Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)\*\*\*Check here if NO logs were run \_\_\_\_\_.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5348 EXPIRATION DATE 6/30/85

OPERATOR Robert E. Campbell API NO. 15-095-21509

ADDRESS 260 N. Rock Road, Suite 110 COUNTY Kingman

Wichita, KS 67206 FIELD K-3

\*\* CONTACT PERSON Robert E. Campbell PROD. FORMATION --  
PHONE 316 685-6001 Indicate if new pay.

PURCHASER N/A LEASE Albrecht

ADDRESS WELL NO. 4

WELL LOCATION 150' NW of C SE NE NE

DRILLING Contractor Mallard Drilling Company 885 Ft. from North Line and

CONTRACTOR ADDRESS 405 Century Plaza Building 435 Ft. from South E Line of

Wichita, KS 67202 the NE (Qtr.) SEC 18 TWP 29S RGE 6W (W).

PLUGGING Contractor Sun Oilwell Cementing

CONTRACTOR ADDRESS P. O. Box 169

Great Bend, KS 67530

TOTAL DEPTH 4182' PBTD --

SPUD DATE 12/18/84 DATE COMPLETED 12/29/84

ELEV: GR 1592' DF -- KB 1600'

DRILLED WITH (X) (ROTARY) (X) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE --

Amount of surface pipe set and cemented 211' DV Tool Used? No

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion -- Other completion -- NGPA filing --

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.


A F F I D A V I T

Robert E. Campbell, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

*Robert E. Campbell*  
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 7th day of February 1985.



*Joyce T. Buss*  
(NOTARY PUBLIC)

MY COMMISSION EXPIRES: 12/20/87

\*\* The person who can be reached by phone regarding any questions concerning this information.

WELL PLAT (Office Use Only)

		18	

KCC   
KGS   
SWD/REP  
PLG.

RECEIVED  
FEB 14 1985  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Side TWO

(E)

OPERATOR Robert E. Campbell LEASE NAME Albrecht #4 SEC 18 TWP 29S RGE 6W (W)  
 WELL NO \_\_\_\_\_

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
Check if no Drill Stem Tests Run. Check if samples sent Geological Survey.			SAMPLE TOPS	
DST#1: 1325-1387; 30-30-30-30; Weak blow; Rec. 15' DM IBHP: 38# IFP: 25# - 25# FBHP: 38# FFP: 25# - 25#			Base Salt Herington Winfield Towanda Ft. Riley Florence	1080 (+ 520) 1297 (+ 303) 1367 (+ 233) 1442 (+ 158) 1485 (+ 115) 1525 (+ 13)
DST#2: 3328-3341; 30-45-60-45; Weak blow thruout; Rec: 70' M Chl: 56,000 IBHP: 1252# IFP: 51# - 38# FBHP: 1227# FFP: 51# - 51#			Funston Crause Red Eagle Foraker Indian Cave	1695 (- 95) 1726 (- 126) 1944 (- 344) 1984 (- 384) 2119 (- 519)
DST#3: 4144-4162; 30-45-90-90; Weak to strong blow; Gauged 8,220 cf/60", 7,510 cf/70" & stabilized Rec: 75' GCM Temp: 128° IFP: 51# - 38# IBHP: 1227# GTS/50" FFP: 51# - 51# FBHP: 1227#			Tarkio Howard Topeka LeCompton Oread Douglas Lansing "A" Zone Swope Hertha Base KC Cherokee Miss Chert Miss Lime Miss Dolo TD	2342 (- 742) 2571 (- 971) 2712 (-1112) 2906 (-1306) 2985 (-1385) 3121 (-1521) 3324 (-1724) 3335 (-1735) 3746 (-2146) 3780 (-2180) 3833 (-2233) 3998 (-2398) 4142 (-2542) 4156 (-2556) 4175 (-2575) 4182 (-2582)
FORMATIONS Soil, shales Shale & lime Lime	0 1784 3207	1784 3207 4182		

RELEASED

APR 20 1987

If additional space is needed use Page 2

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) FROM CONFIDENTIAL

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8	24#	211	60-40 pozmix	35	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Estimated Production-I.P.	Oil bbls.	Gas MCF
Disposition of gas (vented, used on lease or sold)	Water %	Gas-oil ratio bbls. CFPB

Perforations

CONFIDENTIAL

COMPANY: Robert E. Campbell  
CONTRACTOR: MALLARD DRILLING CO., INC.  
405 CENTURY PLAZA BLDG.  
WICHITA, KANSAS 67202

WELL NAME: #4 Albrecht  
DESCRIPTION:  
150' NW of C  
SE NE NE 18-29-6

RIG NO.: 1  
TOTAL DEPTH: 4182'  
COMMENCED: December 18, 1984

COUNTY: Kingman  
ELEVATION: 1592 GL  
COMPLETED: December 29, 1984

CASING RECORD:  
Surface: 5 jts. 8 5/8" x 24# casing  
Production: none

FORMATION	FROM	TO	REMARKS
Soil, shales	0	1784	Ran 5 jts. 8 5/8" x 24# casing set @
Shale and lime	1784	3207	219'. Cement w/ 200 sx 60/40 pozmix
Lime	3207	4182	3% cc, 2% gel. CDNC, approx 10' down.
			Ran 3 Drill Stem Tests
			Plug hole w/ 115 sx 60/40 pozmix, 3% cc, 2% gel, as follows: 1st plug @ 1030' w/ 35 sx. 2nd plug @ 270' w/ 35 sx. 3rd plug @ 60' w/ 25 sx. 10 sx. each mousehole/rathole. Plug down @ 5:00 p.m. 12/29/84.

RECEIVED  
STATE CORPORATION COMMISSION  
RELEASED  
FEB 11 1985  
APR 20 1987  
CONSERVATION DIVISION  
Wichita, Kansas  
FROM CONFIDENTIAL

STATE OF KANSAS )  
                          ) SS.  
COUNTY OF SEDGWICK )

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify  
that this a true and correct copy of the log of the #4 Albrecht  
well, to the best of my knowledge.

  
John Jay Darrah, Jr. President

Subscribed and sworn to before me this 11th day of January, 1985.

  
Notary Public, Patricia C. Byerlee

My commission expires:  
December 11, 1985-

State Geologist Survey  
WICHITA BRANCH