

5 030440.

10-19

155-02654-0600

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 4-26-36
SW, SEC. 35 26 T 23 S, R 4 W X
1460 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5271

Lease Name Goering Well # A-7

Operator: S&K Oil

County Reno 116.68

Name & Address Box 559

Well Total Depth 3590 feet

Tulsa, OK 74101

Conductor Pipe: Size _____ feet

Surface Casing: Size 15-1/2" feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347 Chase, KS 67524

Company to plug at: Hour: 1:22p Day: 22 Month: 9 Year: 19 88

Plugging proposal received from Mike Kelso-Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 8-5/8" @ 3569 w/200 sx - 5-1/2" liner @ 3552 w/125 sx plug back w/sand to 3500' - cap w/5 sx cement - recover available pipe.

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1988

10-31-88
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Ralph Tittel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part top None _____

Operations Completed: Hour: 1:30p Day: 19 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT Shot pipe @ 2700' & recovered - recovered 74' of 8-5/8" - casing hole collapsed @ 180' - tried 1" tubing - could not get further - moved in double drum unit - ran 2 tubing I.H. to 180' - P.T.O.O.H. put on saw tooth collar - ran I.H. - stopped could not rotate and circ. below 155' - P.T.O.O.H. orange peel bottom joint - run I.H. - rotate & circ. to 180' - unable to get farther - cemented w/approx 200 sx 40/60 2% gel, 3% cc. - 5 joints tubing lost in hole.

Remarks: HOWCO #744916-7 B-795062
(If additional description is necessary, use BACK of this form.)

INVOICED
If you did not observe this plugging.

DATE 11-3-88
INV. NO. 228669

Signed Merlan Kurub
(TECHNICIAN)