

3-14

2-040614

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-155-20925-0000

C SW SE, SECTION 14 TOWNSHIP 23 RANGE 9W

OPERATOR LICENSE # 3243 660 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR Commonwealth Petroleum Corp.
NAME & P. O. Box 2458
ADDRESS Hutchinson, KS 67504

LEASE NAME: E Norquist #1
COUNTY: Reno / 122.13
WELL TOTAL DEPTH: 3758'

CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 329'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Darrel Kelso
COMPANY NAME: Kelso Casing Pulling PHONE: _____

WERE: 5-1/2" @ 3772' - sand to 3440' & 5 sx - 35 sx @ 1300'
- 35 sx @ 900' - circ. 380'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 19:15 DAY: 14 MONTH: 3 YEAR: 1990

ACTUAL PLUGGING REPORT:
The open hole was sanded back to 3440' & capped w/5 sx
cmt - pipe was recovered from 2014' & pulled to 1300'
& 35 sx cmt spotted - pipe pulled to 900' where 35 sx
cmt was spotted - pipe pulled to 380' to circ cmt to
surf - cmt circ too soon - hole in pipe - tied on to 8-
5/8" surf and pumped 150 sx cmt .

REMARKS: Allied Cementing #6864 40/60 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 3-15-91

INV. NO. 31168

Steve Van Gieson
Steve Van Gieson (AGENT)

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1991
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90

DW 3-14 MAY 03 1991