

2 100569

2-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-155-20744-0000
C NW SE, SEC. 14, T. 23 S, R. 9W (W/E)
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3243

Lease Name R. Norquist Well # 1

Operator: Commonwealth Petroleum Corp
Name & Address Box 2458
Hutchinson, KS 67504

County Reno 122.36
Well Total Depth 3765 feet
Conductor Pipe: Size 4-1/2 feet 3763
Surface Casing: Size 8-5/8 feet 239

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00a Day: 26 Month: 2 Year: 1990

Plugging proposal received from Darryl Kelso

(company name) Kelso Casing (phone) _____

were: Sand 50' inside 4-1/2" pipe & dump 4 sx cmt - 25 sx @ 1400' - 25 sx @ 900' - 280' circ to surface

Plugging Proposal Received by Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 Day: 26 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT Sanded to 3700' & dumped 4 sx cmt - shot & pulled 2000' of 4-1/2" to 1400' - spotted 25 sx cmt - pulled pipe to 900' & spotted 25 sx cmt - pulled 4-1/2" to 280' & circ to surface with 120 sx cmt.

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1990 3-14-90

Conservation Division
Wichita, Kansas

Remarks: Allied #6162 60/40 4% gel
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and my successors) observe this plugging.

DATE 2-16-90

Signed J. L. Sanders
(TECHNICIAN)

INV. NO. 27688