

2040178

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-155-21091-0000
SW 1/4 SEC. 13, T 23 S, R 9 NE
3680 feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

4620 feet from W/E section line

Operator License # 5073

Lease Name Kernvin Well # 1-13

Operator: Eagle Exploration, Inc.

County Reno 126.75

Name & Address Star Route

Well Total Depth 3900 feet

Pratt Ks 67124

Conductor Pipe: Size _____ feet

Jack Fox

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilg. License Number 5302

Address Wichita Ks.

Company to plug at: Hour: _____ Day: 12 Month: 3 Year: 19 85

Plugging proposal received from Jack Fox

(company name) Eagle Exploration Inc. (phone) _____

were: 35 sx 260'

15 sx 40'

10 sx RH

5 sx WW

Plugging Proposal Received by Stu Chi Gu
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 0100 Day: 14 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Run drill pipe to 260' and circulate the hole full of mud. Spot 35 sacks at 260' and displace with water. Pull drill pipe out of the hole and build a solid Bridge at 40' and circulate the hole with 15 sacks of cement. Circulate 10 sacks of cement in the Rat hole with drill pipe. Plug the Water Well with 5 sacks of cement.

Remarks: Howco 085.593
Additional description (if necessary, use BACK of this form.)
3-26-85

DATE I (did / did not) observe this plugging.

INV. NO. 7428

W.A. MAR 26 1985 Signed Stu Chi Gu
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

CARD MUST BE TYPED

NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 2.....28.....85.....
month day year

API Number 15- 155-21,041

OPERATOR: License # 5073.....

C.N/2 SW NW. Sec 13. Twp 23. S. Rge. 9. *21*

Name Eagle Exploration, Inc.

Address Star Route

City/State/Zip Pratt, KS 67124

Contact Person Jack D. Fox

Phone 316.672.9451

3630..... Ft North from Southeast Corner of Sect
4620..... Ft West from Southeast Corner of Sect
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302.....

Name Red Tiger Drilling

City/State Wichita, KS 67202

Nearest lease or unit boundary line 330.....
County Reno.....

Lease Name Kernvin..... Well# 1-13

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

- | | | | |
|---|-------------------------------|---|--|
| Well Drilled For: | | Well Class: | Type Equipment: |
| <input checked="" type="checkbox"/> Oil | <input type="checkbox"/> Swd | <input checked="" type="checkbox"/> Infield | <input checked="" type="checkbox"/> Mud Rotary |
| <input type="checkbox"/> Gas | <input type="checkbox"/> Inj | <input type="checkbox"/> Pool Ext. | <input type="checkbox"/> Air Rotary |
| <input type="checkbox"/> OWWO | <input type="checkbox"/> Expl | <input type="checkbox"/> Wildcat | <input type="checkbox"/> Cable |

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

Projected Total Depth 3900..... feet

Projected Formation at TD Mississippi.....

Expected Producing Formations Cong.....

Depth to Bottom of fresh water 125-190 mhc

Lowest usable water formation ~~None~~

Depth to Bottom of usable water 100-210 mhc

Surface pipe by Alternate: 1 2

Surface pipe to be set 130-210 mhc

Conductor pipe if any required

Ground surface elevation Est. Elev. 1705..... feet

This Authorization Expires 8-21-85

Approved By 2-21-85 *[Signature]*

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 2/21/85..... Signature of Operator or Agent

Raguel A. Cobles

Title As agent

MHC/LOHE 2-21-85

Form C-1 4-84