

To: 1051133
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20.941-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703

Operator: J.M. Huber Corporation
Name & Address 7120 I-40 West, Suite 232
Amarillo, TX 79106

AP. C E/2 NE, SEC. 9, T 31 S, R 40 W/E
4180 feet from S section line
760 feet from E section line

Lease Name Williams Well # 9-2

County Morton 178.75

Well Total Depth 5500 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1678

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Well Service License Number 5866

Address 7400 East Orchard Road, Suite 370, Englewood, CO 80111

Company to plug at: Hour: 8 a.m. Day: 3 Month: 1 Year: 19 89

Plugging proposal received from Bill Siddens

(company name) J.M. Huber Corporation (phone) 806-353-9837

were: 5 1/2" at 5499' PBTB 5330'-CIBP@ Perfs at 5104-08, 5380-96'
5350' w/20' cmt. to 5330'

spot through tubing
1st plug set CIBP at 5050' with 2 sx cement, 2nd plug at 2350' with 100 sx cement,
3rd plug at 1700' with 50 sx cement, 4th plug at 700' with 50 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:15 p.m. Day: 3 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5050' with 20' cement on top,
2nd plug at 2350-2250' with 100 sx cement,
3rd plug at 1728-1628' with 50 sx cement,
4th plug at 700-600' with 50 sx cement,
5th plug at 40-0' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
2-20-89
FEB 20 1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used Class H cement by Halliburton. Recovered 2850' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If you did not observe this plugging.)

Signed Richard W. Lacey
(TECHNICIAN)

DATE 2-14-89
INV. NO. 23951