

1 020254

9-29

187R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-21,020-0000  
150' NE of  
C NE NW, SEC. 9, T 31 S, R 40 W/E  
4726 feet from S section line  
3194 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703

Lease Name Emberton Well # 9-1

Operator: J.M. Huber Corporation

County Morton 177.91

Name & Address 7120 I-40 West, Suite 232  
Amarillo, TX 79106

Well Total Depth 5474 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1656

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 2:30 p.m. Day: 29 Month: 9 Year: 19 89

Plugging proposal received from Bill Siddens

(company name) J.M. Huber (phone) 806-353-9837

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3287'

1st plug at 2600' with 125 sx cement, 2nd plug at 1686' with 50 sx cement,

3rd plug at 800' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 6 p.m. Day: 29 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2600' with 125 sx cement,

2nd plug at 1686' with 50 sx cement,

3rd plug at 800' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (do not stamp) observe this plugging.

DATE 10-9-89

Signed (Signature) (TECHNICIAN)

INV. NO. 26049

RECEIVED STATE CORPORATION COMMISSION

OCT 05 1989

CONSERVATION DIVISION Wichita, Kansas

Handwritten initials

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 16, 1989 month day year

150' NE of East ... NE of NW. Sec. 9. Twp. 31. S, Rg. 40. West

OPERATOR: License # 5703 Name: J. M. Huber Corporation Address: 7120 I-40 West, Suite 232 City/State/Zip: Amarillo, Texas 79106 Contact Person: William D. Siddens Phone: (806) 353-9837

4726' feet from South line of Section 3194' feet from East line of Section (Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5107 Name: H-30 Drilling Inc.

County: Morton Lease Name: Emberton Well #: 9-1 Field Name: Will-Bros. (Morrow) Is this a Prorated Field? X, yes ... no Target Formation(s): Morrow/Mississippi Nearest lease or unit boundary: 554' Ground Surface Elevation: 3287' feet MSL Domestic well within 330 feet: yes X.. no Municipal well within one mile: yes X.. no Depth to bottom of fresh water: 400' Depth to bottom of usable water: 500' (Permian) Surface Pipe by Alternate: X. 1 ... 2 Length of Surface Pipe Planned to be set: 4500 Length of Conductor pipe required: 40 Projected Total Depth: 5575' Formation at Total Depth: Mississippi Water Source for Drilling Operations: X well ... farm pond ... other

DWR Permit #: Purchased from surface owner Will Cores Be Taken? yes X.. no

If yes, proposed zone: ...

Well Drilled For: Well Class: Type Equipment:

X. Oil ... Inj ... Gas ... Storage ... OIL ... Disposal ... Seismic; ... # of Holes X Infield X Mud Rotary X Pool Ext. Air Rotary Wildcat Cable

If OIL; old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no

If yes, total depth location:

X Pro-verted: Morrow (WILL BROS.)

Exp. 3/14/90

Spud 9-21-89 r 17 00 ft 85 ft

AFFIDAVIT

520' Alt. I Req.

PUSHER Bill Siddens w/ J.M. Huber

Table with columns: TD, FORMATION, SURFACE PIPE, ANHYDRITE, ELEVATION, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ 2600 FT. W/ 125 SX, 2nd PLUG @ 1686 FT. W/ 50 SX, 3rd PLUG @ 800 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ 10 SX, WATER WELL PLUGGED W/ 10 w.w. SX, CEMENT COMPANY, TECHNICIAN S.P., TYPE OF CEMENT 60/40 per w/ 6 gal.

RECEIVED STATE CORPORATION COMMISSION OCT 05 1989 CONSERVATION DIVISION Wichita, Kansas

Grid with numbers 5280 to 330

DATE: 9-21-89 Agent: OB.

- REMEMBER TO: 1. File (Drill Pit Application (form CDP-1) with Intent to Drill; 2. File Completion Form ACO-1 within 120 days of spud date; 3. File acreage attribution plat according to field prorations orders; 4. Notify appropriate district office 48 hours prior to workover or re-entry; 5. Submit plugging report (CP-4) after plugging is completed; 6. Obtain written approval before disposing or injecting salt water.