

To: 1090257
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
209 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-20

API NUMBER 15-129-21,186-6600

App. S/2 NW NW, SEC. 9, T. 31 S, R. 40 W/R

900 feet from N & section line

660 feet from W & section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703

Lease Name Emberton Well # 9-2

Operator: J.M. Huber Corporation

County Morton

Name & Address 7120 I-40 W, Ste. 100

Well Total Depth 5652 183.69 feet

Amarillo, TX 79106

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1674

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: Day: 20 Month: 3 Year: 19 93

Plugging proposal received from Tom Heskett

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Hugoton/Council Grove with 100 sx cement,

2nd plug at 1700' with 50 sx cement, 3rd plug at 575' with 50 sx cement,

4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 p.m. Day: 20 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2600' with 100 sx cement,

2nd plug at 1700' with 50 sx cement,

NOTE: A PLUG WAS ALSO SET AT 4000-3800' FOR A DRILL STEM

3rd plug at 575' with 50 sx cement,

TEST.

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

(check) did not observe this plugging.

DATE 3-31-93

INV. NO. 37522

Signed (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

MAR 26 1993

CONSERVATION DIVISION Wichita, Kansas

EFFECTIVE DATE: 3-2-93

State of Kansas

FORM MUST BE TYPED

FORM MUST BE SIGNED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 129-21,186-0000

ALL BLANKS MUST BE FILLED

FEAS? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 5 1993 ^{Spot} 5/2 NW 9 NW 31 S. Rg 40 X East

OPERATOR: License # 5703
Name: J. M. Huber Corporation
Address: 7120 I-40 West, Suite 100
City/State/Zip: Amarillo, TX 79106
Contact Person: William D. Siddens
Phone: (806) 353-9837

CONTRACTOR: License #: 30606
Name: Murfin Drilling Company

Well Drilled For: X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic: ... # of Holes ... Other

If OWWO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth ...

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth: ...
Bottom Hole Location: ...

900 feet from South / North line of Section
660 feet from East / West line of Section
IS SECTION X REGULAR ... IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Marton
Lease Name: Emberton Well #: 9-2
Field Name: WillBros
Is this a Prorated/Spaced Field? X yes ... no
Target Formation(s): Morrow/Mississippi
Nearest lease or unit boundary: 660
Ground Surface Elevation: 3297 feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 400
Depth to bottom of usable water: 560 (T. Permian)
Surface Pipe by Alternate: ... 1 ... 2
Length of Surface Pipe Planned to be set: (1600') 580
Length of Conductor pipe required: ...
Projected Total Depth: 5860
Formation at Total Depth: Mississippi
Water Source for Drilling Operations: ... well ... farm pond X other
DWR Permit #: Purchase from surface owner
Will Cores Be Taken?: ... yes X no
If yes, proposed zone: ...

AFFIDAVIT

580' Alt. I Req.

Exp. 8/25/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-424

Pusher Tom H. Smith INIT. CH

SPUD DATE 3-5-93

LENGTH SURFACE PLANNED 1675

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y SIZE HOLE
SURFACE PIPE 8 3/4 CONDUCTOR
ANHYDRITE T- B ELEVATION

TD 5652 FORMATION

RAN PIPE @ <u>SX</u>	DV TOOL	ALT II DONE
	<u>SX</u>	<u>Y</u> <u>N</u>
<u>Arbuckle Plug @</u>	<u>Ft. W/</u>	<u>SX</u>
<u>Hug./Council @ 2600</u>	<u>Ft. W/ 100</u>	<u>SX</u>
<u>Anhydrite Base @ 1700</u>	<u>Ft. W/ 50</u>	<u>SX</u>
<u>1/2 Base Anhy. @ 515</u>	<u>Ft. W/ 50</u>	<u>SX</u>
<u>1/2, 1/2 Plug @</u>	<u>Ft. W/</u>	<u>SX</u>
<u>Bottom Surface @</u>	<u>Ft. W/</u>	<u>SX</u>
<u>40' Plug @ 40</u>	<u>Ft. W/ 10</u>	<u>SX</u>
RAT HOLE CIRC/W <u>15</u> SX	MOUSE HOLE W/ <u>10</u>	SX

WATER WELL SX (Irr. Well ... Pond ...)
Hauling

TECHNICIAN SM DATE 3-18-93

TYPE OF CEMENT 60/40%

STARTING TIME MAR 28 1993 (AM/PM) DATE

COMPLETION TIME ... (AM/PM) DATE 3:20

WICHITA DIVISION
KANSAS CORPORATION COMMISSION