

1020859

5-3

API NUMBER 15- 129-21,350-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW, SEC. 9, T 31 S, R 40 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Baughman D Well # 1
County Morton 182.65
Well Total Depth 5620 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1635

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address: P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 3 Month: 5 Year: 1995
Plugging proposal received from Kirby Lillard

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 5620' w/360 sx cement, Perfs at 4484-90', CIBPs at 5400', 4700'
1st plug at 4484-4434' with 25 sx cement, 2nd plug at cut-off with 20 sx cement,
3rd plug at 1685-1585' with 50 sx cement, 4th plug at 40-5' with 12 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4 p.m. Day: 3 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5400',
2nd plug set CIBP at 4700', 3rd plug pumped 2 sx hulls and 25 sx cement at perfs, displaced
with mud, 4th plug pumped 50 sx cement at 1670',
5th plug pumped 40 sx cement at 700',
6th plug spotted 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 1940' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (if desired, observe this plugging.)

DATE 5-15-95

INV. NO. 42824

Signed Glenn R. Barlow (TECHNICIAN)