

11-19-87

To: 6 020425
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-20,322 *W. CO. 01*
SEC. 6, T 14 S, R 29 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: Donald C. Slawson
Name & Address: 200 Douglas Bldg.
Wichita, Kansas 67202

Lease Name Zerr S Well # 1
County Gove *146.25*
Well Total Depth 4500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling License Number 5657
Address G.B. Ks.

Company to plug at: Hour: 2:00AM Day: 19 Month: Nov Year: 19 87

Plugging proposal received from Bob Rowl
(company name) _____ (phone) _____

were: Order 190 sks 60/40 Poz 6% Gel 3% Ca Cl 1 sk Flocele and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by *Gilbert Balthazor*
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8:00PM Day: 19 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT
1st plug at 2175' w/25 sks Anhy
2nd plug at 1160' w/100 sks and 1 sk F.C. *RECEIVED STATE CORPORATION COMMISSION*
3rd plug at 290' w/40 sks *JAN 18 1988*
4th plug at 40' w/10 sks/wiper *0 25*
15 sks in rat hole *2: W 250-280*
3. 955 - 1000

Remarks: Cemented by Allied.
(If additional description is necessary, use BACK of this form.)

~~Inspector~~ did not observe this plugging.

Signed *Gilbert Balthazor*
(TECHNICIAN)
Gilbert Balthazor

INVOICED
DATE 1-20-88
INV. NO. 19617

CARD MUST BE TYPED

State of Kansas

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

[Handwritten Signature]

(see rules on reverse side)

Expected Spud Date... November 14 1987

API Number 15- 063-20,322-A.00.01

OPERATOR: License # 5181
Name... SLAWSON, DONALD C.
Address... 200 Douglas Building
City/State/Zip... Wichita, Kansas 67202
Contact Person... Bill Horigan
Phone... (316) 263-3201

...C. NW. NW. Sec. 6... Twp. 14. S, Rg. 29... East
4620' Ft. from South Line of Section
4620' Ft. from East Line of Section

CONTRACTOR: License # 5657
Name... Slawson Drilg. Co.
City/State... Great Bend, Kansas

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 660' feet
County... Gove

Well Drilled For: Well Class: Type Equipment:
 Oil Storage Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Lease Name... ZEBB 'S' Well #... 1
Ground surface elevation 2735' GR. (L&S) feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator... CHIEF DRILLING CO., INC.
Well Name #1 ZEBB
Comp Date... 2/16/77... Old Total Depth... 4230'

Depth to bottom of fresh water... 200'
Depth to bottom of usable water... 1200'
Surface pipe by Alternate: 1 2
Surface pipe planned to be set... 273' Already set.
Conductor pipe required
Projected Total Depth... 4500' feet
Formation... MISSISSIPPIAN

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date... 11/13/87... Signature of Operator or Agent

Western Kansas
Robert B. Jenkins Title... District Geologist

For KCC Use:
Conductor Pipe Required... feet: Minimum Surface Pipe Required... 273
This Authorization Expires 11-5-88

Approved By 11-13-87 feet per Alt. 2

EFFECTIVE DATE: 11-18-87

Bob Rowe spud 11/16/87

273' S.P.

Starting zone

Marion took

...C. NW. NW. Sec. 6... Twp. 14. S, Rg. 29... East

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

| | | |
|------------------------------------------|---------------------------|---------------------------------------|
| 1st plug @ ft. deep... 2250' | or formation with... 40sx | feet of... 60/40 Poz. w/6% Ge1 |
| 2nd plug @ ft. deep... 1200' | or formation with... 75sx | feet of... 60/40 Poz. w/6% Ge1 |
| 3rd plug @ ft. deep... 400' | or formation with... 40sx | feet of... 60/40 Poz. w/6% Ge1 |
| 4th plug @ ft. deep... 40' | or formation with... 10sx | feet of... 60/40 Poz. w/6% Ge1 |
| 5th plug @ ft. deep | or formation with | feet of |
| (2) Rathole to surface minus 5 feet 10sx | | (b) Mousehole to surface minus 5 feet |

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.
In Addition: Call district office before well is either plugged or production casing is cemented in.
(Call 7 a.m. to 5 p.m. workdays)

RECEIVED

STATE CORPORATION COMMISSION

JAN 18 1988

District office use only:

API #15- 063-20,322-A

CONSERVATION DIVISION
Wichita, Kansas

Surface casing of... feet set with... sxs at... hours, 19

Alternate 1 or 2 surface pipe was used.

Alternate 2 cementing was completed @... ft. depth with... sxs on... 19

Hole plugged... 19... agent... KCC District #8

NOV 16 1987

Form C-1 11/86

Hays, KS