

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-19067-00-02
Spot: NENENW Sec/Twnshp/Rge: 12-6S-18W
4928 feet from S Section Line, 2940 feet from E Section Line
Lease Name: FAUBION Well #: 1
County: ROOKS Total Vertical Depth: 3238 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	5.5	3037		
PROD	7	3037	175	sx
SURF	10	1330		

Well Type: SWD UIC Docket No: D21061.0 Date/Time to Plug: 11/21/2012 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: Ordered 420 sx 60/40 pozmix 4% gel cement w/750 # hulls.
Tagged T.O. at 1210' with tubing.
Perforated at 800' and 350'.
Completed on 1-13-36 by Gillespie and Sons Co.
15 1/2" at 37'
12 1/2" at 1065'.
10" at 1330'
7" at 3037' w/75 sx cement. Perforated at 1125' w/800 sx cement.
5 1/2" liner from 3037' to 1122'.
PBTD at 1122'. Cedar Hills SWD
Perforations from 973' - 1057'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2012 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Hooked to 10"x 7 1/2" annulus and pumped 30 sx cement. Shut in pressure 200 psi.
Ran tubing to 1195' and pumped 250 sx cement w/400 # hulls to circulate to surface.
Pulled all tubing. Hooked to 5 1/2" casing and pumped 130 sx cement w/350 # hulls.
11/26/12- Topped off 5 1/2" casing with 10 sx cement.

Received
KANSAS CORPORATION COMMISSION
JUN 29 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE FAUBION #1 FEE FUND PROJECT CONTROL # 20130032-001

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM