

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-049-00238-0000
 Spot: SW/NE/SW Sec 12 Twp 31 S Rng 8 ☒ E / ☐ W
1627 Feet from ☐ N / ☒ S Line of Section
3700 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 37.364515 Long: -95.483652 Date: 5/20/14
 Lease Name: TRIBOULET (Schrader 1929) Well #: EDT 03 (TRI 03)
 County: Elk Total Vertical Depth: 1205 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>KANSAS CORPORATION COMMISSION</u>	<u>DRIVE - Drive Pipe</u>	<u>18.000</u>			
Address 1: <u>226 N MAIN STE 220</u>	<u>T1 - Tubing 1</u>	<u>9.000</u>			
Address 2: _____	<u>T2 - Tubing 2</u>	<u>3.000</u>			
City: <u>WICHITA</u>	<u>T3 - Tubing 3</u>	<u>1.500</u>			
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: GAS - Natural Gas - Production UIC Docket No.: _____ Date/Time to Plug: 1/12/16
 Plug Co License No.: 33749 Plug Co. Name: KWS
 Proposal Revd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-9212

Proposed Plugging Report: **CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.**

Plugging Proposal Received By: TOMBILYEU Witness Type: PART - Partial
 Date/Time Plugging Completed: 1/12/16 / _____ KCC Agent: TOMBILYEU

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
DUG OUT SURFACE AND FOUND 10" INSIDE 12" INSIDE 8" WITH 3" AND 1.5" INSIDE. SET A 20" SURFACE AND SET UP. PULLED ON 1.5" ON PACKER AND PIPE SPLIT. PULLED SURFACE OUT AND DUG DEEPER CUT 3" OFF TO GET TO 1.5". RAN COLLAR LOCATOR AND SHOT OFF 1.5" AND PULLED. WASH DOWN OUTSIDE OF 3" TO 1205' AND 600' INSIDE. PUMPED 232 SACKS OF CEMENT. TAGGED NEXT DAY AND PUMPED 262 SACKS OF CEMENT. THE LOCATION WAS RESTORED.		<u>1086</u>		
		<u>890</u>		
		<u>590</u>		

Remarks: CONTRACT#38595;CONTROL#20160015-003;CAT#3;NAD 83;GPS BY TONY

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☐ No

District: 03

Received
KANSAS CORPORATION COMMISSION

Tom Bilyeu
(Technician)

JUN 01 2016

CONSERVATION DIVISION
WICHITA, KS

Form: District Plugging Report - _____