

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21261-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 2-34S-20W  
2970 feet from S Section Line, 4302 feet from E Section Line  
Lease Name: SELZER Well #: 1  
County: COMANCHE Total Vertical Depth: 5270 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5092		WITH 10 SX CMT
COND	13.375	129		WITH 225 SX CMT
PROD	4.5	5261	1234	WITH 225 SX CMT
SURF	8.625	667		WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2016 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Set CIBP @ 5092', circulate hole with mud and cap CIBP with 10 sks cement. Weld on 7" pull sub. Cut & free pipe.  
Spot the following cement plugs: a) @ 860' spot 60-sks cement. b) @ 320' spot 40 sks cement. c) @ 64' - 4' spot 20 sks cement. Cut & Cap well. Dig up rig anchors.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2016 9:45 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

6/8/16: SET CIBP @ 5092' WITH 10 SX CMT. RAN TBG TO 860' & PUMPED 80 SX CMT. NO CIRCULATION. SHUT DOWN 2 HOURS. WENT IN TO TAG. NOTHING THERE. PUMPED ANOTHER 80 SX CMT. NO CIRCULATION. SHUT DOWN. TAGGED CMT AT 753'. SPOT 50 SX CMT AT 750'. SDON. 6/9/16: TAGGED CMT AT 551'. PUMP 40 SX CMT AT 320'. PUMP 20 SX CMT AT 64'. CMT CIRCULATED.

Top	Bot	Thru	Comments
5142	5146		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SEND\*\* USED CLASS A CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Larry Harris ECRS  
SW (TECHNICIAN)

RECEIVED  
JUN 10 2016  
KCC DODGE CITY

NO  
JUL -7 2016 Form CP-2/3