

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19251-00-00
Spot: SWSENE Sec/Twnshp/Rge: 13-26S-4E
2937 feet from S Section Line, 904 feet from E Section Line
Lease Name: TAGUE Well #: 2
County: BUTLER Total Vertical Depth: 2497 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2492		0 SX
SURF	8.625	85		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2016 12:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: LEVI KOEHN Company: BRUCE OIL CO Phone: (620) 241-2938

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL
Date/Time Plugging Completed: 04/07/2016 2:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

ABD. ARBUCKLE WELL FROM CIRCA 1951, UNKNOWN WHEN LAST PRODUCED. WELL WAS NOT SHUT IN. 4/5/2016 (KCC WITNESSED). 1) RIGGED UP OVER HOLE, RAN IN W/TBG AND HIT BRIDGE AT 150', PULLED OUT OF HOLE AND PUT DRILL COLLAR ON. 2) RAN IN HOLE W/BIT, WASHED DOWN TO APPROX. 550' AND HIT UNKNOWN, SOLID BRIDGE. DRILLED THROUGH BRIDGE, DOWN TO 612'. 3) FROM 612' APPROX. 750', HARD DRILLING. CIRCULATING SCALING AND GRAY FLAKES. APPEARS TO BE CIRCULATING DRILL MUD, TUBING STRING POSSIBLY OUTSIDE OF CASING. 4) PULLED OUT OF HOLE - PULLED 25K GETTING CLEAR, LAST 3 TUBING JOINTS HAVE SIGN OF DRILL MUD ON OUTSIDE - DETERMINED LIKELY OUTSIDE OF CASING APPROX 612'. 4/6/2016 (KCC NOT WITNESSED, BUT UPDATED ON WORK BEING PERFORMED) 1) RAN IN HOLE W/SMALL IMPRESSION BLOCK, DID NOT MAKE IT PAST OBSTRUCTION AT APPROX. 610'. MOLD NOT CLEAR WHAT OBSTRUCTION WAS. 2) RAN IN HOLE W/ TAPERED MILL TO 600', MILLED FOR 4 HOURS - NO DEPTH MADE, NO CHANGE IN RETURNS, HOLE REMAINING FULL. 3) PULLED OUT OF HOLE, ATTEMPTED TO RUN 1" ON BACKSIDE OF 5.5" CASING, APPROX. 10' DOWN SOLID ALL AROUND, DETERMINED TO BE CEMENT. DUE TO CEMENT ON BACKSIDE AND DETERIORATING HOLE CONDITONS, DECISION MADE TO PLUG W/O BOTTOM PLUG INSTALLED. 4) RAN TUBING BACK IN TO APPROX. 600' AND PUMPED 73 SXS CLASS A CEMENT WITH W/2% CACL, CIRCUALTED CEMENT TO SURFACE. 4/7/2016 (KCC WITNESSED). VERIFIED CEMENT AT SURFACE INSIDE 5.5" CASING. CASING TO BE CUT DOWN AND BURIED AND PIT FILLED IN.

Perfs:

Top	Bot	Thru	Comments
2492	2497	OH	

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, EL DORADO, KS. TICKET #: 51703.

Plugged through: TBG

District: 02

Signed Jonathan Hill

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN) NO

JUN 23 2016

JUL -7 2016

CONSERVATION DIVISION
WICHITA, KS