

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-19013-00-00  
Spot: N2NWSE Sec/Twnshp/Rge: 1-31S-9W  
2310 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: LYDIA I GAUG Well #: 3-1  
County: HARPER Total Vertical Depth: 4520 feet

Operator License No.: 34357  
Op Name: ATLAS OPERATING LLC  
Address: 15603 KUYKENDAHL, STE 200  
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4478		
PROD	5.5	4519		200 SX
SURF	8.625	350		275 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2016 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/22/2016 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PULLED ROD & PUMP. TUBING STUCK BELOW 3100'. PERF'D TUBING AT 4430' & PUMPED 50 SX CEMENT 3% CACL. RECOVERED TUBING FROM 3108' & LAYED DOWN. RAN E-LINE TO 1500' & PERF'D. PERF'D AT 1000' & 400'. RAN TUBING TO 1500' SPOTTED 35 SX CEMENT. TAGGED CEMENT AT 1270'. PULLED TUBING TO 1000' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 400' & CIR'D CEMENT TO 0' WITH 185 SX CEMENT.

Perfs:


Top	Bot	Thru	Comments
4488	4494		
4444	4460		

Remarks: QUALITY WELL SERVICE. COMMON CEMENT. DENIED TA

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

KCC WICHITA  
JUL 05 2016  
RECEIVED

Form CP-2/3  
JUL -7 2016