

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-20325-00-00
Spot: NWSWSESW Sec/Twnshp/Rge: 2-31S-9W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MILLER ESTATE Well #: 1
County: HARPER Total Vertical Depth: 4490 feet

Operator License No.: 34357
Op Name: ATLAS OPERATING LLC
Address: 15603 KUYKENDAHL, STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4489		125 SX
SURF	8.625	215		225 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/06/2016 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHRD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/13/2016 12:00 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

RAN IN HOLE WITH BAILER, STACKED OUT 3530'. TIHWT & NOTCHED COLLAR, COULD NOT DRILL OUT. LAYED DOWN RAN IN HOLE WITH COLLARS & BIT, DRILLED 1 FOOT IN 2 HOURS, LOST CIRCULATION, PUMPED 50 SX CEMENT AT 3537', SET OVERNITE, TAGGED AT 3450'. SHOT PERF HOLE AT 1500', 1000' & 260'. RAN TUBING TO 1500' SPOTTED 50 SX CEMENT. TAGGED CEMENT AT 700'. SPOTTED 60 SX 700', PULLED TUBING TO 265' & CIRCUALTED TO 0' WITH 105 SX CEMENT, SET OVERNITE, PULL CASING & ANNULAS WITH 80 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4408	4414		

Remarks: QWS COMMON 3% CACL. DENIED TA

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUN 23 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUL -7 2016