

7-16

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-095-00813-0001

SW SW, SECTION 19 TOWNSHIP 29 RANGE 6W

OPERATOR LICENSE # 5123 660 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR Pickrell Drilling Co.
NAME & 110 N. Market #205
ADDRESS Wichita, KS 67202

RECEIVED
KANSAS CORPORATION COMMISSION

LEASE NAME: Cox B-2
COUNTY: Kingman
WELL TOTAL DEPTH: 4501' 146.26

JUL 30 1993 7-30-93

CONSERVATION DIVISION
WICHITA, KS

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 208'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clarke Corporation
ADDRESS: P.O. Box 187 Medicine Lodge, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Jeff Stiletto

COMPANY NAME: Clark Corporation PHONE: 316-668-5665

WERE: 35sx @ 1100', 35sx @ 700', circ @ 260', 5-1/2 4485',
Perfs 4100'-4110', CIBP 4030', Perfs 3717-19'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 12:00 DAY: 16 MONTH: 7 YEAR: 1993

ACTUAL PLUGGING REPORT:

A CIBP was set at 4030' to covered Mississippi perfs-
sand was used to cover the KC perfs back to 3650' and
capped with 5 sx of cmt- the 5-1/2" was recovered from
2656' and pulled to 1110' where 35sx of cmt was spotted
- the pipe was pulled up to 717' where 35sx of cmt was
again spotted- the pipe was pulled to 260' where cmt
was circ to surface- the remaining pipe was pulled
from the wellbore and the cmt was topped off.

REMARKS: Allied cmt #1568 Common Cmt

INVOICED

DID OBSERVE THIS PLUGGING.

DATE AUG 04 1993
382.55

Steve Van Gieson

Steve Van Gieson (AGENT)