

303-980-1154 11-24-86  
2 040372

API NUMBER 13-095-01,006-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C. NW SW, SEC. 19, T. 29 S, R. 6 WXX

1978 So. Garrison 1980 feet from S section line  
TECHNICIAN'S PLUGGING REPORT 8.102 80227 4620 feet from E section line

Operator License # 5481

Lease Name Cox Well # 1-19

Operator: Grant Oil Company

County Kingman 147.71

Name & Address 3190 S. Wadsworth Blvd.

Well Total Depth 4545 feet

Lakewood, CO 80226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well Input Well SMD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Gabbert & Jones License Number

Address

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Max Deem

(company name) Gabbert & Jones (phone)

were: 35 sxs @800', 35 sxs @260', 15 sxs @40', 15 sxs in rathole.

Plugging Proposal Received by Steve Van Gieson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 13:15 Day: 24 Month: 11 Year: 1986

ACTUAL PLUGGING REPORT The drill pipe was run to 800' where 35 sxs cement was spotted in place. The drill pipe was pulled to 260' where 35 sxs cement was spotted. The drill pipe was pulled to 40' where 15 sxs was spotted. The rathole was circulated with 15 sxs cement.

STATE CORPORATION COMMISSION

NOV 2 1987 11-02-87

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 11-9-87

Signed Steve Van Gieson  
(TECHNICIAN)

WV. NO. 18765

11-24